BRUHAT BANGALORE MAHANAGARA PALIKE

FORM OF EXTRA ITEM RATE LIST IN FORM NO. P.W.G.71.

Name of Work: PROVIDING SEATING STEPS TO GALLERY AT SWAMY VIVEKANANDA PARK IN WARD NO-3 BBMP BANGALORE
Estimate Amount:- 50,00,000.00
Name of Agency:- Sri.G.T.Rajegowda
Approved amount:- 5423174/-
Tender Premium 11.76% Above

Sl. No.	Description of work	Unit	Asper qty	Rate	Amount	Whether the items are alternative to the item in the tender, whether these are additional items or sometimes in Accepted tender	Whether the extra items are included in the sanctioned estimate	How the extra cost of the item is proposed to be met	Whether the cost of the item is included in the CSR, if not a Data Rate has to be derived	Remarks
1	2	3	4	5	6	7	8	9	10	11
1	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. with all lead and lift and directions of the Engineer in charge of the work	Sqm	248.13	727.38	180484.50	Yes	No	Under the savings of the Sanctioned Estimate	Yes	Suggestions By Site Engineer & PMC
2	Providing and laying of Granite slabs of 7.5cms of thickness to Gallery steps and Erecting of stuss and purlins using crane.(crane charges per day)	Sqm	10.00	4470.40	44704.00	Yes	No	Under the savings of the Sanctioned Estimate	Yes	do
3	Providing 2 legged scaffolding for stone masonry work using 10-15 cms. dia best quality casurina poles of 4m over all length (3m +0.5m projection + 0.5m In to the ground), the distance between two rows being 1.25m and spacing of	Sqm	1071.60	242.52	259883.57	Yes	No	Under the savings of the Sanctioned Estimate	Yes	do
	Total				**485072.07**					

Note:% Excess over the amount put to tender = EIRL Amount / Amount Put to tender x 100
(485072.07 / 4852456.61)*100 = 9.99%

Executive Engineer
Project Division
Yelahanka Zone, BBMP